


COMPONENTISED INTERNAL WALLS FOR MULTI-RESIDENTIAL APPLICATIONS CRC #28 FINAL REPORT









Australian Government Department of Industry, Science, Energy and Resources AusIndustry Cooperative Research Centres Program

CONTENTS

1.	EXECUTIVE SUMMARY	02
2.	RESEARCH APPROACH 2.1 Multi-scalar thinking 3.2 Expert panels and interviews 3.3 Design research / Provocations	04
3.	 PROBLEM DEFINITION 3.1 Overview of BAU 3.2 Common failures and redundancies 3.3 Waste and life cycle 3.4 OH&S related to internal walls 	06
4.	 EXEMPLARS AND ALTERNATIVES 4.1 Scope and method of case studies 4.2 Themes emerging from exemplars 4.3 Multi-scalar mapping of BAU and alternatives 	12
5.	 PROVOCATIONS 5.1 Literature review - barriers to adoption 5.2 Lessons from provocations improvements to BAU performance sleeve plug and play no walls 	18
6.	 RECOMMENDATIONS 6.1 Key findings 6.2 Research gaps to be addressed in long-term project 6.3 Partners for future research 	28
7.	APPENDIX 7.1 Provocations: design and assessment 7.2 Exemplars and alternatives 7.3 Performance and life cycle 7.4 Workshops and outcomes 7.5 Interviews	32

7.6 Student work from studies unit Wall Party!

CONFIDENTIAL:	X _{No} Yes			
Author of this report:	Laura Harper, Lee-anne Khor, Jean-Paul Rollo			
Date of this report:	14th Dec 2023			
Project completion date:	20th Dec 2022			
Program Leader reviewer:	Duncan Maxwell			
Project Title:	Componentised Internal Walls for Multi-Residential Applications			
Project Duration:	6 Months			
Partners:	 Lendlease Digital Monash University Melbourne University 			
Project team members:	 Monash University: Dr Laura Harper, Dr Lee-Anne Khor, Dr Duncan Maxwell, Dr Ivana Kuzmanovska and Dr Victor Bunster, Jean-Paul Rollo and Daniela Tinios. Lendlease: Karl-Heinz Weiss, Stephen Huang and Daiman Otto University of Melbourne: Prof. Tuan Ngo, Dr Xuemei Liu, Dr Yousef Alquaryouti 			
Acknowledgments:	• The authors gratefully acknowledge the contributions of the expert panel members Prof. Nigel Bertram, Prof. Shane Murray, Prof. Daphne Flynn, Prof. Nelson Lam, Dr Rachel Couper and Dr Rowen Page.			
	• The authors acknowledge the contributions of Masters of Architecture students Zahra Aamiry, Aggelos Avramopoulos, Anne Barlow, Sylvanna Dong, Aidan Fiore, Ali Hashemian, Rose Kheng Lot, Annabelle Low, Ameil Mekha, Daryl Neff, Scott Rowe, Arran Roxburgh, Matthew Smith, Taylar Stanton, Zoe Swoboda, Alexander Troup, John Tsitouridis, Tung Vo			
	Drawings and images by Monash Urban Lab, unless otherwise noted.			

Disclaimer

The Building 4.0 CRC has endeavoured to ensure that all information in this publication is correct. It makes no warranty with regard to the accuracy of the information provided and will not be liable if the information is inaccurate, incomplete or out of date nor be liable for any direct or indirect damages arising from its use. The contents of this publication should not be used as a substitute for seeking independent professional advice.

1. EXECUTIVE SUMMARY

This report outlines the findings from a scoping study into Componentised and Connected Internal Walls for Multi-residential applications. The research identified a set of multi-scalar issues associated with businessas-usual (BAU) approaches to internal walls including defects and rectification costs; on-site waste (up to 18% in the case of plasterboard); and associated incidents leading to common injuries. A literature review into the benefits of prefabrication indicated that componentised wall systems could help address these key issues.

The scoping study developed a framework for assessing the efficacy of componentised wall alternatives. The design-led research identified knowledge gaps that impede the take-up of prefabrication within existing design, manufacture, assembly and delivery processes. These inputs and processes will be the focus of a second stage of research development, and include: new modes of reporting with industry to quantify tangential costs associated with common issues such as defects and OH&S; strategies for overcoming barriers such as ingrained procurement practices; on site tolerance issues; and lack of digital integration from design through to manufacture. The report recommends that future research include partners across the supply chain to establish workable responses to these barriers.

Overview of research question

Typical internal wall systems in multi-residential buildings are commonly achieved through multi-layer plasterboard wall systems. Elements in these wall systems are handled, cut and assembled on site and require multiple trades to complete the structural, services and finishing required. These wall systems are labour intensive, and involve wasteful on-site processing – quality control is difficult to achieve. The described performance requirements for internal walls including fire and sound separation rely on skilled trades and supervision - when these fail, significant and costly legacy issues arise. Componentised wall systems which address these issues are common in other sectors such as commercial fitouts - so why aren't these being pursued for internal walls in residential construction?

Team and approach

Project #28 is a collaboration between Monash University's Urban Lab and Future Building Initiative, with engineering input from the University of Melbourne and working closely with industry partner Lendlease. We utilised three key methods:

- industry consultation through interviews and workshops
- a literature review including a survey of existing componentised wall systems and lifecycle assessment tools
- a design research approach to put forward scenarios for review and discussion.

Literature review

Our literature review supported industry feedback on key issues with business-as-usual wall construction.

Defects

- Significant and growing costs are associated with defects rectification annually.¹ A large portion of serious defects include those relating to issues with passive fire separation, i.e. faults in fire-seals within inter-tenancy walls.²
- Findings are limited in their accuracy and relevance by the way defects are reported and catergorised. Future research could establish methods of analysing project data to support a more nuanced understanding.

OH&S

- Installation of plasterboard has been directly linked to OH&S injuries, primarily with musculo-skeletal disorders (MSDs).³ MSDs account for the most common of series injuries (16%) within the construction sector.⁴
- Research suggests that off-site manufacturing reduces OH&S incidents by reducing exposure to common risks.⁵

Plasterboard waste and lifecycle assessment (LCA)

- Significant waste (between 12% to 18%)⁶ is built in to the installation of standard plasterboard wall panels.
- Suppliers report that pre-cut plasterboard solutions are available why don't contractors explore these?
- Existing LCA tools and data operate on overall building scales and systems; assessing internal walls in isolation requires new data and approaches.

Summary of findings

By testing the design research led scenarios, or provocations, we found that shifts towards componentisation could address many of the BAU issues identified, but significant barriers to adoption remain. The following opportunities, barriers and recommendations reflect results from the design research led scenarios.

OPPORTUNITIES

- Componentised wall systems could reduce the time, complexity and waste of on site construction, offering considerable cost advantages.
- Any shift to off-site construction would reduce OH&S incidents (namely musculo-skeletal disorders) linked directly to handling plasterboard on site.
- Initiatives such as utilising a 'performance sleeve' (refer 5.2 Lessons from provocations below) could significantly reduce serious defects associated with failures in fire and sound separation.
- The use of bio-materials to replace common walling materials (for example strawboard replacing Hebel) has the potential to reduce carbon footprint, or even carbon capture, creating important contributions to sustainability.
- The introduction of a fully off-site product for walls allows for repair, flexibility and replacement, enabling significant value to be retained over time. This may be particularly suited to scenarios such as a build-to-rent.

BARRIERS TO ADOPTION


- Lack of digital integration with services, suppliers and manufacturers raises questions about industry readiness for off-site solutions.
- Costing models for internal walls do not currently factor in tangential costs such as defect rectification and decanting. Until they do so, a shift to componentised walls is unlikely to stack up financially.
- BAU internal fitout does not require walls to be craned etc while pre-assembled solutions may, raising the possibility of implications for BAU critical path planning.
- Current practice builds in tolerances to account for • deviation from documented design due to inaccuracies.

How can the precision of off-site manufacture come together with variation on site?

Pre-assembly and/or off-site integration of services would require a location, transport and personnel - i.e. a third party. Who would this be?

RECOMMENDATIONS

- Improve collection and analysis of data to quantify costs associated with internal walls including evidence-based analysis of defects, OH&S, digital integration, supply chain mapping and critical path planning.
- Investigate digital processes including survey existing BIM platforms used by partners, exemplars and examples.
- Expand design research and prototype testing into different building typologies and structural systems, including testing junction details.
- Expand the research to involve partners across the supply chain to understand how workable solutions to barriers in componentised walls might be overcome.



over main performance wall. Reduced duration and complexity of trades on site.


2. RESEARCH APPROACH

Research for project # 28 was undertaken through three key methods. Industry consultation was gathered through a series of discussions, workshops and interviews. This provided anecdotal, first hand experiences of the problems associated with internal walls in an Australian context which informed our subsequent research approach. A literature review was undertaken to establish a foundation for gathering industry feedback about on-site issues with internal walls (such as reported OH&S incidents), as well as to identify documented barriers to achieving higher levels of prefabrication. Part of this literature review included a survey of existing componentised wall products and alternatives. Finally, design research methods were employed to propose scenarios or 'provocations' which responded to existing problems. Analysis of these scenarios with industry partners enabled us to reveal the interconnected and complex issues which currently form barriers to the use of componentised wall systems in multi-residential applications.

2.1 Industry consultation

Industry expertise and multidisciplinary academic inputs were sought throughout the project through structured workshops as well as recorded interviews. Two half-day workshops, conducted via zoom, included selected personnel from within the Lendlease team as well as an invited panel consisting of academic experts, practising architects and designers. An introductory paper was issued to participants (CRC28 EP1 Report) and discussion was structured around prepared visual materials via online collaboration tool MURAL. Expert panel 1 (EP1) focused on a discussion of issues and opportunities. We presented work through a multi-scalar mapping of issues across the construction process comparing common BAU approaches to alternatives that we had identified and studied. Participants responded through written feedback which was recorded, organised and disseminated back to the panel. EP2, conducted in a similar format, focused on LCA with specific discussion on new business models such as Build-to-rent and their potential to shift equations of costs. Outcomes of workshops are detailed in Appendix 7.4.

A series of interviews were planned for the scoping study - these were only partially completed. COVID lockdowns and restrictions posed significant hurdles for planned in-person events including interviews, site visits and visits to supplier and manufacturer plants. The record of transcripts from interviews is not available to the public.



Discussion board from Expert Panel 1. (Refer Appendix 7.4, EP1)

2.2 Literature review and case study analysis

A literature review was undertaken to survey existing relevant research. A key focus was on understanding existing research into barriers to the adoption of componentised systems. Identified papers were summarised and key issues drawn out to construct a diagram of barriers to adoption that exist across the industry. A key finding of the literature review was that although significant research exists about barriers to the adoption of prefabrication more broadly, specific literature addressing internal walls was harder to find. Literature also provided an evidence base to support anecdotal experiences reported from industry. For example, significant recent research into quantities and types of defects in the construction industry can assist in quantifying the scope of this issue. Future research recommendations include understanding how project data is currently reported and accounted for within partner organisations, and if possible, to design methods for collecting this kind of data to support future research evidence.


A key research activity was a survey of pre-existing approaches to componentised wall systems. In line with the design research led approach, the initial survey of precedents is broad and draws on examples across time and industries. It examines not only the details and materials of particular wall systems, but also the factors and conditions that make them viable and suitable for particular applications at particular times. A full list of systems and themes studied to date is included in Appendix 7.2

2.3 Design research and provocations

Design research focuses on an open-ended exploration of options rather than solutions based approaches driven by current constraints. Design research is described as learning through doing - by applying ideas to real world situations and context, the issues and opportunities can be both revealed and communicated to others.⁷


An initial use of design research was tested through the integration of a Masters of Architecture design studio and studies unit. The brief to students ran in parallel to the research project, providing students with the opportunity to work with a real-world issue and to have input from industry partners. The studio work, typically representing a more 'blue-sky' approach to the issue was also presented to industry partners and acted as a useful discussion point to develop themes and ideas.

We also used a design research led approach to propose a series of four scenarios, or provocations, which were then presented to industry partners and relevant academics for review. These provocations were also tested, on paper, by University of Melbourne in terms of performance certification. The provocations serve as a way to communicate both the challenges and potential of componentised wall systems. For example, provocation 1 examined small changes in BAU construction and exposed hidden issues in the procurement process, such as existing trade subcontracts that prevented initiatives like off-site cutting to take place.



AXONOMETRIC DIAGR

An example of the drawings undertaken of existing componentised wall system. Detail from student examination of 'Packaged House System, Konrad Wachsmann and Walter Gropius, 1939'. (Refer Appendix 7.2)



Sketch detail of provocation 1, which tried to understand barriers to simple improvements to BAU such as precutting of plasterboard.

3. PROBLEM DEFINITION

Internal wall systems in multi-residential construction continue to rely on labour intensive and wasteful onsite processing despite advances in prefabrication in other aspects of this type of construction. Described performance requirements for internal walls rely heavily on skilled trades and supervision - when these fail, significant and costly legacy issues⁸ arise. Quality in execution, services integration, services penetration through walls, cracks in joints and subsequent performance issues have been identified by industry partner Lendlease as having significant costs that are not currently factored into project costing models. Further research also identified significant waste production (industry average of plasterboard waste generated on site is circa 18%), associated OH&S incidents relating to handling and cutting of plasterboard and implications of construction sequencing as internal walls hit the critical path at the end of construction. Together, these issues point to a multi-scalar set of issues impacting internal walls.

3.1 Overview of internal wall systems

Internal partitioning in multi-residential construction is typically achieved with plasterboard wall systems which consist of a stud frame (either timber or steel) with a layer of plasterboard which forms the surface finish. Insulation and other layers are included depending on performance requirements. These walls are non-load bearing and can be either within a single apartment (intra-tenancy), between two adjacent dwellings (inter-tenancy) or adjoining a common area. Additionally they may hold services or not. The range of performance requirements for different internal wall applications has been met by varying the way frames, insulation/cores and surfaces are configured. Put simply, the amount, thickness, spacing and treatment of materials may change, but the underlying logic of drywall construction remains unchanged (See adjacent Figure 'Summary of internal non-load bearing wall types').


The classification of wall types and performance requirements does not necessarily pair with the spatial hierarchies of multi-residential building typologies, such as common access areas or dwelling ownership. More stringent performance requirements are set between bedrooms than for partitioning of private and common space, for example. A comprehensive analysis of performance requirements was undertaken for this project (Appendix 7.3).

The make-up of typical plasterboard walls requires processing materials on site, and complex assembly processes involving tools, equipment and trades. On-site activities include measurement, cutting, positioning and fixing of plasterboard surfaces, which are susceptible to damage at each stage. Movement between multiple 'workstations' (e.g. for dust containment), double handling for on-site adjustments, as well as uncovering and re-finishing work for the coordination of trades, present time and cost redundancies and generate a considerable amount waste (discussed further below). Proprietary wall systems are accompanied by increasingly onerous dimensional accuracy and fixing techniques nominated by suppliers to meet performance requirements. An example is the standard Hebel inter-tenancy wall detail (refer p.9). The technical rigidity of constraint-driven wall solutions, combined with the complexity of on-site processing and delivery, leads to a number of compliance failures.

Summary of internal non-load bearing wall types in multi-residential construction including overview of performance requirements which are applied depending on the location of walls within the building.

Wall type


Partition (within dwelling)






Typical construction


Inter-tenancy



Common areas, corridor



Services, 'wet' walls



Performance requirements

Acoustic separation

The acoustic privacy required by various spaces is dependent upon:

- the noise level generated within the source room
- the degree to which legibility is acceptable within the receiving room or space.
- Wall System Ratings must be considered in conjunction with Background Noise Levels.

Fire resistance Level (FRL)

Determined with respect to the structural adequacy, insulation, and integrity performance criteria. In non-load bearing walls, the latter two criteria govern the fire performance, as studs are capable of withstanding the self-weight of the wall system. FRL improvement achieved by:

- gap clearance and emissivity
- reduction of plasterboard degradation
- confinement of plasterboard moisture.

Thermal comfort

The energy required to heat and cool residential buildings has significant environmental impacts. Maintaining "comfortable" thermal conditions with active systems (ventilation and air-conditioning) is the largest sector in energy consumption in most of the developed world (Griffiths et al 1988). In multi-residential projects, an average Nationwide House Energy Rating Scheme (NatHERS) rating of 7 Stars or greater is required.

Air tightness (transfer of smells)

Minimise uncontrolled movement of air through the walls, roof, floor and joinery to achieve healthy indoor air quality and energy efficiency. Reduced air infiltration:

- saves energy required for heating/ cooling appliances
- eliminates contamination of the indoor air
- prevents mould and mildew in the construction from internally driven moisture
- enables controlled ventilation.

3.2 Common failures and defects


Defects are an inevitable occurrence post construction on every building site and are an accepted part of the building process.⁹ A construction defect is defined as 'a defect in the workmanship, design and/or in the materials or systems used on a project that results in a failure of a component part of a building or structure, which, in turn causes damage to the property or person'.¹⁰


Successful installation of plasterboard wall systems relies on skilled trades. Performance requirements are dependent on the order of material layers, the number and type of fixings, the correct application of fire and acoustic seals around penetrations and at junctions, and the continuity of insulation. Performance can be compromised through small variations to multiple aspects of the system. Compounding the complexity of internal wall systems are the multiple trades and therefore people who are part of completing the system. Installation of studs, services rough-in, installation of plasterboard, services finishing and painting are often installed by separate teams which attend site in sequence.

A significant amount of research exists documenting the frequency, type, severity and causes of defects in the construction industry.¹¹ Sandayake et al. (2022) documented a rapid increase in research attention to the issue of defect rectification in the construction industry in the past two decades. Defects have been the subject of mainstream media attention, particularly in NSW and the ACT where sustained public attention has influenced building defects reform.¹²

Understanding what percentage of defects relate to internal walls is difficult given the way in which defects are recorded, documented and analysed. In their comprehensive Examination of Building Defects in Residential Multi-owned Properties, Johnston and Reid (2019) outlined the complexity of classifying and organising defects and the different ways in which defects are reported.¹³ Their own data, drawn from defect audit reports provided by multiple building consultants / auditing companies, provided some insights into defects that can be linked to internal walls. For example they found 13% of defects (the second largest category after building envelope) related to defects with fire separation. Within the category of fire separation, about half (45%) were the result of passive fire protection measures - namely improperly installed fire seals and fire collars within intra-tenancy walls.¹⁴ This is just one of the many potential defects raised by industry partners in relation to plasterboard walls. Defects relating to failure of sound separation for example, which Lendlease noted as a common (and difficult to fix) building defect, were not separately catergorised in Johnston and Reid.


It is clear that existing research supports industry reports relating to defects within internal walls, however it is difficult to apply this research directly to internal walls. Future research should aim for a more targeted approach to quantifying these issues, for example through an analysis of defects data within an organisation, or by project.





Common causes of failures and defects in business as usual internal wall construction.

- **Corner + connection details:** Staggered corner joints misaligned; plasterboard often doesn't run through. Leads to thermal and acoustic performance failures, and potential for physical/visual defects to emerge.
- **Cavities:** Specific spacing dimensions for Hebel panels to achieve acoustic performance; level of accuracy / lack of tolerance leads to common spacing errors. Incorrect installation leads to cavities acting as sound amplifiers.
- Services: Integration within wall system construction, as well as subsequent penetrations required, are a common source of errors/wall damage requiring rectification and cost imposts. Access to concealed services presents challenges for maintenance and adaptations over a dwelling's life span.
- Material delivery: Redundancies exist in the distribution of materials to active building levels and work locations. Vertical transport platforms deliver goods and equipment to a central loading point, from where they are manually carried up/down to adjacent floors (nom. 2 or 3 levels) and manually manoeuvred to relevant workstations (e.g. cutting occurs in a separated area for dust containment). The multiple movement patterns and handling present inefficient operational costs and risks damage to panels.
- Acoustic seals to top/bottom plates: Frequently omitted requiring costly rectification of performance defects (often only observed post-occupancy).
- **Panel joints:** Vertical or horizontal joints. To achieve performance requirements, product manuals call for a specific number of screws per panel, with nominated spacing dimensions. Divergence from specifications is very common.
- **Insulation gaps:** Smallest compromise impacts performance to such an extent that it may as well not be installed.
- **Decanting Costs:** Costs associated with rectifying these defects include not only the repair of the walls themselves but also the costs of decanting and rehousing residents temporarily.



3.3 Waste and lifecycle


Plasterboard is typically purchased in standard sheet sizes - a commonly utilised sheet size is 1200mm wide by 2400mm high. The mismatch between standard sizes and variation on building sites inevitably leads to a gap where waste is produced. Estimates of the amount of plasterboard wasted through off-cuts on site vary. In the USA this has been estimated at 12%.¹⁵

The National Waste report 2020 estimated Australia produces 74.1 million tonnes (Mt) of waste per year, 44% (or 27Mt) of which is linked to the construction and demolition (C&D) sector.¹⁶ While other wastes have declined in the past decade, waste associated with C&D have risen, linked to rapid levels of development in major cities. While over 80% of C&D waste is recycled (largely demolition and excavation waste used for road base and fill for civil projects), the construction industry remains a key contributor to material entering into the waste processing system. In contrast to other core waste, C&D waste consists of both used waste (demolition waste) as well as off-cuts of material which have never been used such as plasterboard.

Waste reduction or prevention is seen as the most effective form of mitigating waste. The Waste Hierarchy establishes a set of priorities for actions that can be taken to mitigate waste.¹⁷ At the top of the inverted pyramid is waste reduction, followed by reuse, then repair, recycle, recovery and disposal. The factors at the top of the pyramid tend to have the lowest impact on the environment while the lower priority actions, although important, each have significant impacts and waste associated with them. For example, energy required to recycle materials, and to transport materials to waste recovery centres, reduces the overall benefits of recycling. Research has documented that off-site manufacturing and digitisation of building more broadly has great potential to promote more efficient use of materials and produce less waste.¹⁸

This project comes at a time when both industry and government are investing significantly in methods for mitigating waste. For example, in 2018, Federal, state and local governments agreed on the 2018 National Waste Policy and in 2019 this was followed by the 2019 National Waste Action Plan which outlines a strategy for moving Australia towards a circular economy by 2030 including waste reduction targets and significant commitments to investing in recycling technologies. The Federal Government's \$190 million Recycling Modernisation Fund is an example.¹⁹ Industry are also investing in developing circular economy approaches. Examples of this include CSR Plasterboard take-back scheme,²⁰ and the cross-industry joint venture announced by Asahi Beverages, the PACT Group and Cleanaway group for a new plastics recycling facility to process their own and others' product waste.²¹ Factors for this investment are varied and linked to both expectations of investors and the public, as well as to global influences. Australian exports of waste products intended for recycling have fallen sharply in recent years, linked to new import restrictions from China and other Asian nations implemented in 2017.²²

Lendlease have their own targets for carbon reduction but more work is required to understand how these could be considered as a project cost.







The Waste Hierarchy. Source: Waste Framework Directive, European Commission

3.4 Health and safety


The construction industry is one of the highest risk workplaces in Australia. According to Safe Work Australia, the construction industry records three workplace fatalities per 100,000 workers and 8.1 serious claims per million hours worked.²³ Many workplaces have targets for reduction in OH&S incidents on site.

Plasterboard has been identified by Safe Work Australia as being a key contributor to musculo-skeletal disorders (MSDs) due in large part to its ubiquitous use on almost every building site.²⁴ Workers compensation data highlights that MSDs are the most common serious non-fatal injuries (16%) within the construction sector, and dominate claims for workers compensation.²⁵

MSDs are largely caused by hazardous manual tasks including lifting, picking up and lowering heavy objects and materials. In standard sheet sizes, plasterboard is bulky and is frequently handled manually in confined spaces, making movement and lifting awkward. Installation of plasterboard on ceilings was identified as a particularly difficult manual task requiring both installation at heights as well as lifting and handling - all tasks associated with high risk of injury.

The potential for off-site manufacturing to reduce incidents with OH&S is often reported as one of primary benefits of this mode of construction. The logic is that many incidents happen in the variable and unpredictable conditions of on-site construction and that the controlled environment of the factory will therefore reduce incidents which occur. However Odo and Rankin (2022) noted a lack of quantifiable data to support the improved safety of off-site construction.²⁶ In their 2022 study, Odo and Rankin compared on-site and off-site construction occurring simultaneously on a mid-rise building utilising both methods. They developed a model for assessing risks associated with types of activities across the whole of the supply chain - a method which allows for a direct comparison between off-site and on-site construction. These activities were assigned a risk likelihood, severity and exposure drawn from statistical OH&S incident reporting.²⁷ The findings demonstrated that workers in on site situations have a much higher exposure to common activities with statistically quantifiable OH&S risks, demonstrating the overall improvements to OH&S of manufacturing off site.

The research into OH&S demonstrates that more work needs to be done to quantify both the risks associated with BAU approaches to internal walls, as well as to understand and communicate the potential improvements to OH&S of off-site construction. Future research in this project should learn from the model develop by Odo and Rankin (2022) as a start to begin processes within organisations to link the costs of OH&S to innovations in construction methodology.



4. EXEMPLARS AND ALTERNATIVES

We reviewed, documented and analysed over 70 examples of componentised wall systems from contemporary and historical sources. We developed themes through the analysis and categorisation of these exemplars which focus attention on the key attributes of different componentised walls including: digital integration across the supply chain; integration of walls with floor and ceiling systems; removable / replaceable wall panels and many more. These themes correspond to challenges identified with BAU approaches and have informed the development of the four design research provocations. They also inform the recommendations of this report for future research.

4.1 Methodology for review of exemplars and alternatives

An important aspect of base research for this project was the broad selection of componetised wall systems, details and materials for analysis, as well as a consistent and rigorous approach to understanding the factors and conditions informing each situation. The study of a large number of precedents was undertaken through a series of themes including:


- pioneers of prefabrication including 20th century experimental post-war modular design
- modular furniture and partition systems from other industries such as office fitouts and hospital design
- commercially available modular systems including modular pods, demountable buildings and relief housing
- contemporary experimental approaches including architectural designs and advanced manufacturing.

The survey of precedents was run in parallel with, and informed the curriculum for, the Masters of Architecture studies unit, 'Wall Party!'. The students' research provided an initial survey of examples which then enabled the research team to test methods of documentation, comparison and categorisation and create a refined list.

We developed a written and drawn database which details the systems studied and how they perform against specific aspects of design and construction. (Refer Appendix 7.2 for full database.) The process of categorisation helped to draw out and understand common design questions that modular and componentised approaches to walls must solve. For example, how does a standard dimension deal with corner situations? The following section shows examples of categories developed through comparison and analysis of the systems, and particular precedent examples which demonstrate different approaches to these categories. These are not a full list of categories nor precedents but rather an example of the way in which a range of precedents from different applications and time periods become relevant when exploring particular aspects of modular wall design. The full and visual database is presented in Appendix 7.3.



A sample of the open ended database collected by students (Refer Appendix 7.2)




Documentation of componentised house system Maison Tropicale by Jean Prouve, 1951. Drawings by Masters of Architecture students Annabelle Low, Anne Barlow and John Tsitouridis. (Refer Appendix 7.2)


			Wall type			
Wall system name	Designer	Year	Application	Approach to services	Dimension of Parts	Flexibility
Siniat Residential	Siniat	2021	Intertenancy wall	not-serviced	small unit (one person)	Permanent / no flexibility
SpeedPanel	SpeedPanel	2021	Internal partition	not-serviced	mechanical assistance	Whole panel demountable
Smart-wall telescopic	Rondo	2021	Internal partition	Integrated on-site (conduits)	small unit (two people)	designed to be moveable
DIRTT	DIRTT	2021	Internal partition	integrated with serviced floor	small unit (two people)	cladding removeable
Maison Tropicale	Jean Prouve	1951	External wall	not-serviced	small unit (two people)	Whole panel demountable
Katsura Imperial Villa	Hachijo Toshihito	1624	Internal partition	not-serviced	small unit (two people)	designed to be moveable
Dymaxion House	Buckminster Fuller	1944	External wall	Integrated on-site (conduits)	mechanical assistance	Permanent / no flexibility
Packaged House System	Wachsmann & Gropius	1942	External+IT+Partition	not-serviced	small unit (two people)	Whole panel demountable
Schröder House	Gerrit Rietveld	1924	Internal partition	not-serviced	small unit (two people)	fold-away furniture elements
USM	USM Haller	1965	Internal partition	not-serviced	small unit (one person)	cladding removeable
Modscape	Modscape	2021	External+IT+Partition	Integrated off-site	small unit (two people)	Permanent / no flexibility
SIPS	SPA	1996	External wall	Integrated on-site (conduits)	mechanical assistance	Permanent / no flexibility
Dincel	Dincel	1989	External+IT+Partition	Integrated on-site (conduits)	small unit (two people)	Permanent / no flexibility
Royal Academy of Arts	Gilles Restin	2019	Experimental design	not-serviced	small unit (one person)	Whole panel demountable
Wikihouse	Open source	2011	External+IT+Partition	Integrated on-site (conduits)	small unit (two people)	Permanent / no flexibility
Full Fill Homes	Anupama Kundoo	2015	External wall	not-serviced	small unit (two people)	Whole panel demountable
School Pod	Gollifer Langston	2008	Experimental design	Integrated on-site (conduits)	mechanical assistance	Whole panel demountable


Example of categorisation and analysis of componentised wall system allowing a searchable database.

4.2 Themes emerging from exemplars and alternatives



- Digital integration of supply chain from design to manufacture and delivery.
 An example is the ICE platform which enables designers to work with standard
 - components and details through a BIM platform with real-time calculation of bill of materials and delivery schedules.
- Smart junctions at joints, floor and ceiling, which provide a prefab integrated solution to weak points in performance.
- An example is the enduring USM Haller furniture system which provides a universal joint for all points on the frame into which panelised surfaces clip.
- Pre-integration of services enabled by digital integration between design and factory, and services consultants.
- An example is the DIRTT preassembled steel stud partition system which comes to site pre-serviced and ready to plug and play.
- New bio-materials offer potential to reduce CO₂ and improve performance.
- An example is Ortech's Durra Panel product, manufactured locally in Bendigo from compressed straw which provides negative carbon impacts and improves fire, thermal and sound insulation.
- Replaceable surface panels allow for repair and upgrade over time.
- An example is the FastMount removable wall system designed for commercial applications which allows surface panels to be repaired and upgraded or even swapped out with technology enabled smart panels.























- An example is the Rondo Smartwall Telescopic which allows steel stud systems to be height variable to deal with site conditions.
- Wall integrated with floor and ceiling systems including for services.
- An example is DIRTT Power, a modular grid system of raised tiles that allows services to run below the floor, enabling flexibility and adaptability of walls.
- Advanced manufacturing allows new possibilities in componentised walls.
 An example is the Wikihouse an open source kit of parts. Every component in
 - the house can be produced through a digital file input to a CNC machine.
- Pod technology enabling sections of interiors to be fully prefabricated and serviced.
- An example is the Schiavello Modular fully serviced bathroom pod, which can be inserted into floor plates.
- Smart panels with Integrated tech which activates surfaces for electricity, heating and cooling technologies.
- An example is the 3D printed electrics pioneered for aviation wall panels by Airbus to apply smart technology to thin surfaces.
















4.2 Multi-scalar mapping of alternatives (below) compared with BAU (above)



This diagram maps alternatives compared to BAU, across multiple areas raised by this research project. Each individual drawing can also be found at a larger scale elsewhere in this report.



5. PROVOCATIONS

We tested barriers and opportunities through a set of four provocations - speculative wall designs that addressed issues identified in the problem definition, and attended to emerging themes and opportunities developed through a study of exemplars. The provocations proved useful in discussing potential improvements offered by different approaches to componentised walls, revealing real and contextual issues to their adoption, and identifying areas where more research is required. In this report we use them to frame the potential advantages as well as barriers to the adoption of componentised walls.


5.1 Methodology

Design research uses an applied methodology to test outcomes against real-world conditions. With these provocations, our aim was to propose actual wall systems that could be assessed, tested and considered against the issues and opportunities of componentised walls. Each provocation draws on specific issues identified through the problem definition and proposes methods to address them. They also draw on the opportunities and themes identified through the study of exemplars as a means to find solutions to address particular issues. By drawing and detailing these provocations, we could test them against performance requirements, building layouts, costs and build-ability.

An example is provocation 2 – performance sleeve. This provocation specifically sets out to solve the issue of defects associated with services penetrations in BAU approaches to internal walls. In BAU approaches, performance relies on the exact installation of layers, seals, insulation and fixings to achieve desired fire and sound separation. Services penetrations through and within these elements create performance failures and rely on conscientious craftsmanship to ensure separation is not compromised. The concept of the performance sleeve is to provide independence to performance requirements. An inner wall layer, or 'performance core', achieves all separation requirements whilst never interrupted by services. The finishing surface 'sleeve' is not critical to performance needs, and services can dictate penetrations.

To test whether the performance sleeve idea was viable, we designed a wall build up based on existing materials and systems and drew up details to show how layers would be constructed on site. Engineers from the University of Melbourne then tested and assessed these details for performance requirements, as well as lifecycle costing so that we could compare our proposed wall system with BAU. We could also estimate costs for each material. This applied testing enabled an assessment of the viability of options, and the kinds of issues associated with the general approach.


The provocations also proved invaluable as discussion points with partners and experts which drew out issues we had not considered. An example is provocation 1 – improved BAU – which proposes simple improvements such as pre-cutting of plasterboard. As we discussed this provocation with the team, it became evident that there was a lack of clarity around when, how and from whom plasterboard was procured – establishing more information about procurement practices became a central recommendation of this report.



Testing concepts through applied design details allowed real world limitations and issues to be revealed and discussed

Product Name	Durra Panel S50 Plain		
Nominal Thickness	50mm		
Weight	18.5 kg/m² (nominal)		
Width (Standard)	1187mm		
Maximum Length	3600mm		
Face Colour	Brown (Kraft liner)		
Strength	Point load 5.8kN		
Impact Resistance	High		
Thermal Conductivity	0.081 W/mK		
Thermal Resistance	0.62 m²W/k		
Specific Heat Capacity	1050 J/kgK		
Embodied Energy	12.6 MJ/m ²		
VOC Emission rate (ASTM D5116)	<0.05 mg/m²/hr (7 days		
Biscuit Slots	Available		

Componentised wall details were tested for performance and cost, with inner wall layers made up of materials with high specification efficiencies such as Durra Panel. Durra Panel Specification source: Ortech Industries, Technical Manual: Durra Panel, Durra Steel Sections, Panelised Building Systems. 03.10.2017, Section 1.3.4. Matrix of four provocations and their findings



5.2 Lessons from provocations

Provocation 1 - Improved BAU

This provocation is based on identifying simple initiatives to adjust existing BAU wall systems, shifting elements of the process off site without changing the essential material build up or challenging existing performance methods. Shifts proposed are:

- pre-cutting (by the manufacturer) of standard materials including plasterboard, Hebel and steel studs
- pre-assembly of stud frame including installation of services runs.

Findings

The research identified that simple changes to BAU internal wall systems are currently available and could be implemented immediately. Such initiatives could be beneficial in addressing identified issues, but continue to face barriers.

Opportunities


- Reduce waste (and thereby costs) on site. Potential waste savings could equal current over-order (i.e. 12-18%).
- Smaller pre-cut board sizes would reduce OH&S incidents (namely musculoskeletal disorders) linked directly to handling plasterboard on site.
- Pre-assembly of studs could reduce OH&S incidents on site associated with cutting, and if craned, eliminate incidents relating to handling.
- Pre-assembly of services locations and insulation into studs could reduce defects associated with penetrations.
- Reducing time on site generally may contribute to improved time costs associated with sequencing (refer to Appendix 7.1 for more information).

Barriers


- Current practice builds in large tolerances to account for deviation from documented design due to on site inaccuracies, increasing the risk of pre-cutting and raising the question of who would bear this risk.
- There is a lack of clarity around the internal processes used for procurement within organisations. Why aren't pre-cut solutions being applied already? What procurement structures make pre-cut solutions difficult to implement?
- BAU internal fitout does not require craning while pre-assembled solutions may, raising the possibility of implications for BAU critical path planning.
- Pre-assembly and/or off-site integration of services would require a location, transport and personnel i.e. a third party. Who would this be?
- Lack of digital integration with services information, or with suppliers and manufacturers raises questions about industry readiness for off-site solutions.

Limitations

Provocation 1 would not address the issue of serious defects associated with the complexity of achieving performance through BAU approaches to internal walls.





Sketch showing simple changes to BAU wall systems; pre-cut plasterboard and pre-cut frame; shifting some parts of the process off site.



BAU details look the same for *Provocation 1: Improved BAU* but efficiency and handling time is significantly improved through pre-cutting and organisation of services off silte prior to delivery.

Timeline showing sequence of trades to complete fitout in BAU (above) and Improved BAU (below)





Internal fitout becomes time critical at the end of construction for multi-storey residential buildings, when all other trades are complete - Lendlease referred to this as 'the last 100 days'. Any off site efficiencies to reduce the time for the final floor fitout has potential for significant cost and time benefits. These diagrams demonstrate improvements offered by precutting of materials and off site installation of services.

Provocation 2 - Performance sleeve

This provocation is based on the concept of an inner material layer which achieves all performance requirements and is not penetrated by services. This approach decouples performance from both surface and services cavity, allowing simplification of fitout sequence and reducing trades responsible for achieving performance.

We tested this provocation through the design of a wall build-up using two layers of Ortech Durra Panel - a compressed straw panel which achieved all performance requirements according to University of Melbourne testing (see Appendix 7.2). Over this base wall achieving performance, a cavity created through non-structural steel battens holds services and a surface panel fulfills a finishing role only.

Findings

The research noted a performance sleeve could have significant benefits but identified barriers to what would constitute quite a significant shift from BAU approaches.

Opportunities


- A performance sleeve could make significant improvements to reducing serious defects, for example those associated with fire and sound separation.
- Services installation and subsequent finishing could be streamlined by reducing penetrations through performance layers.
- New bio-materials such as strawboard have potential as a performance sleeve due to the way they perform in fire, sound and thermal protection.
- The notion of a sleeve, which continues part or full way across the ceiling and floor, has potential to address flanking issues particularly relevant in timber or steel structural applications.
- Decoupling performance from the surface layer and services has potential to improve defects rectification, as well as to repair and alter aspects of interiors.

Barriers


- The sleeve constitutes a significant shift from BAU, raising questions about its viability relating to existing skills and practices within the industry. Potentially this may require a separate installer (as is the practice for Durra Panel).
- The overall thickness of the wall including a performance sleeve would need to approach current wall thickness to avoid losing too much floor area.
- Costs associated with alternative materials such as strawboard would need to be quantified - a method to factor in value from improvements as described above is likely required to make an argument for a significant shift in logic.
- Performance could be achieved with differing levels of off site logic more study would be required to understand implications for sequencing etc. Cranage may be required depending on weight of panels etc.

Limitations


The performance wall system shown here is designed to address issues with intertenancy walls only. Further research could relate to partition wall build-ups.



Sketch showing the concept of a performance sleeve, where performance is decoupled from both the services cavity and the finished surface.



Example detail section of performance build up using two layers of Durra Panel separated with an air gap. The performance layer is shown here continuing along floor and ceiling to deal with flanking issues. Finishing sleeve is composed of plywood sheeting.



Key principles for the performance sleeve provocation: fire, thermal and acoustic comfort are achieved by wrapping the inner wall or 'performance core' with a finishing 'sleeve'; services penetrations cut holes into finishing surfaces only.

performance core: performance within inner wall layer

interchangable (clip system)

Provocation 3 - Plug and play

Provocation 3 recognises that not all internal walls are equal - intra-tenancy walls are free of many of the performance and property requirements that inter-tenancy walls must achieve. The plug and play option exploits the potential freedom of partitions from services with the exception of electrical and pushes these partitions to be as thin, light and flexible as possible. We tested this provocation through the design of a hollow steel framed partition with low current electric circuits installed on the inner face of the metal panel infill.

Findings

The research found this option could deal with issues of waste by proposing a product that retains residual value over time because it can be reused, repaired and adapted rather than demolished and constructed anew. This product could be particularly focused towards build-to-rent options where longevity is valued, and walls may be reconfigured to suit changing households over time.

Opportunities


- This option reduces waste on site, and over time by implementing a product style system that retains value. This may be particularly suited to scenarios where longevity is valued such as a build-to-rent situation.
- It increased flexibility of interiors over time, allowing for layouts to be re-configured.
- Like fixtures, this design can be easily removed, upgraded, replaced or changed.

Barriers


- While flexible and upgradeable solutions are feasible in commercial situations, given the reasonably static nature of residential interiors, does a flexible system make sense?
- Products based on longevity need a corresponding business model to make sense build-to-rent may provide that context.
- A plug and play solution to electric services would require integration with a ceiling or floor.
- Questions were raised around who would make, own, service and install these specialised products. Do products exist which fulfill similar requirements and could these be tested for residential applications?
- Questions of sound insulation in intra-tenancy walls remain.
- Issues arise between a modular system and a non-modular building design. Would this type of system only work within a modular building or could it be adaptable to site conditions?

Limitations


Provocation 3 deals only with internal partitions. It demonstrates a product based approach to walls as a provocation to consider how questions of longevity may impact how we consider internal walls. However, such a solution requires a dedicated fabricator / third party. Existing solutions could be identified or adapted from other industries such as commercial fitouts.




Sketch showing how a 'plug and play; wall could be achieved through a steel frame and clad solution.



A modular plug and play solution would require apartment layout to be designed to accommodate.





Electrical runs along floor or ceiling can give freedom to wall locations and options for future adaptation.

Provocation 4 - No walls

This provocation is based on leveraging existing pod technology to consider how to eliminate internal walls altogether. Extensive research and development has been given to the topic of services pods, including within the Building 4.0 CRC team. Pods are being utilised in construction across different sectors. This provocation suggests that apartments could be divided by performance enabled pods along party walls, and divided internally by furniture and services pods. We tested examples provided by Lendlease. Some of these were able to be adopted to pod designs.

Findings

The research found that division within apartments could be achieved entirely through furniture and services pods - but only within some apartment footprints. Pods for division of interiors would also face similar challenges to bathroom pod installation.

Opportunities


- The completion of interiors entirely through the insertion of serviced and finished pods poses that same potential as bathroom pods to eliminate a series of difficult and time consuming trades and activities from site.
- As with any completely off-site solution to internal walls, benefits would be gained through reduction of OH&S incidents and waste.
- Serviced pods, if designed to achieve inter-tenancy performance requirements, could address issues associated with on-site performance quality.

Barriers


- Significant issues have been identified in the installation of bathroom pods which have prevented successful adoption of this technology across the industry.
 Project #31 explored these in more detail.
- How compliance is achieved in off-site systems remains unclear. Does compliance still rely on the finishing of junctions to ceiling and floor, and ultimately remain an on-site issue?
- Using pods as a division for apartments only works for some apartment layouts. Apartment design and layout would need to be considered with pods in mind from the beginning of the design phase.

Limitations


No walls deals with multiple issues of internal walls by removing them and replacing them with pods. Like provocation 3, such a solution requires a dedicated fabricator / third party to be viable.



Could all requirements for internal walls be achieved through pods?



The use of furniture pods would also require apartment design to be adapted to suit.



Back to back kitchen pods can be detailed to provide required performance along inter-tenancy walls, including consideration of raised floors to accomodate services.

6. RECOMMENDATIONS

The findings from section 5 lead to a series of recommendations for future research. A key recommendation is on improving data collection and analysis to provide more targeted and meaningful evidence to support potential improvements to issues such as OH&S and defects. A case based approach to future research would assist in developing such data.

Digital integration across supply chains and with consultants is noted as a key issue for any innovation in componentised wall. The report recommends attention to this aspect in future research.


Noting the integrated issues across the supply chain for realising even the most simple of off-site improvements, the report recommends future research include suppliers, manufacturers and organisations 'in the middle' of the supply chain to find meaningful responses to identified barriers.

6.1 Improved collection, categorisation and analysis of data

At the outset of project #28, the plan was to analyse real project data and visit case studies on site to understand issues around defects, OH&S and other factors. This proved difficult, in large part due to COVID restrictions, but also due to the timeframes required to set up such consultations processes with large partner organisations. Literature reviews on identified issues were useful to support in broad terms the issues raised by partner organisations. More meaningful findings though, would be created through analysis of project and/or organisation data.

A key recommendation is to establish a case study approach to future research in which project data from partner organisations can be analysed across the lifespan from design through to construction. Specific data around the costs of current issues will support the argument for a shift to componentised walls, and provide the inputs to develop a costing model which is able to factor in the long-term and ongoing costs of particular approaches to internal walls. Such an approach should be supported by a framework to provide consistent metrics and a database to provide industry wide access. Specific data which would assist includes:

- OH&S incidents catergorised by activity. This can assist in comparing on-site and off-site potentials for OH&S improvements.
- Defects catergorised by type, location and impact from defects rectification period, as well as over the lifespan of the building warranty. This can assist in isolating the number and seriousness of defects associated with internal wall construction.
- Project mapping of procurement decision making who, when and how are decisions about material supply made. This type of information may be best understood by following a 'live' project in the procurement phase.
- Mapping of critical path planning to understand the relationship of activities associated with internal walls and when they are, or are not on the critical path in construction. Attention is also required on crane time to understand implications for larger pre-assembled components to be lifted.



6.2 Attention to digital processes

A repeating issue arising from the provocations was the need for digital integration for the implementation of any form of off-site construction. An important recommendation therefore is a survey of partner organisations to understand Building Information Management (BIM) currently in place, and to what extent consultants and suppliers are connected to these platforms. Key questions in relation to this survey include:

- When are BIM platforms used by partner organisations in the construction process, i.e. is it part of the design, documentation and ordering process and how it is connected, if at all, to costing models and procurement of building elements?
- Who is connected to BIM platforms? Does it extend from designers to consultants, construction managers, suppliers and manufacturers?
- What exemplars exist for digital integration across the supply chain and what can we learn from these examples?

6.3 Expanded design research and prototype testing


Design research allowed the testing of example componentised walls at the level of the system and detail. An expanded approach would build on this basis including:

- Test componentised systems within existing / proposed (real examples) building plans in different types of residential buildings to understand implications for layout, dimensionality and detailing.
- Apply specific componentised walls to different structural conditions including concrete, timber and steel frame options
- Work through provocation 1 improved BAU with reference to a specific project with attention to when decisions are made regarding supply of materials.
- Establish comparative models for build-to-sell and build-to-rent conditions. How does this shift the requirements and investment in internal walls?
- Explore existing and local componentised wall options against partner projects. How do costs stack up in relation to BAU? What are the issues when componentised systems meet BAU on-site conditions?


6.4 Partners across the supply chain

An essential aspect of the research is the recognition that that any initiatives to increase off-site processing of walls or to install componentised systems will rely on others in the supply chain. This may include manufacturers of base components, subcontractors who assemble systems and components and also suppliers and installers. For this project, key partners may include:


- Plasterboard manufacturers
- Steel stud manufacturers
- Suppliers of wall systems (Rondo, Knauf etc.)
- Manufacturers of associated products including insulation, fire seals, fixings and others who contribute to the overall performance of internal walls.



More research is required to understand existing and possible innovations with digital integration.



Expanded design research will test different building typologies and structure models.



The interconnected nature of internal wall construction will benefit from expanding partners across the supply chain.

Endnotes

- 1 Malindu Sandanayake et al., "Residential building defects investigation and mitigation a comparative review in Victoria, Australia, for understanding the way forward," *Engineering, Construction and Architectural Management*, Vol. 29 No. 9, (2022): 3689-3711. https://doi. org/10.1108/ECAM-03-2021-0232
- 2 Nicole Johnston and Sacha Reid, An Examination of Building Defects in Residential Multi-Owned Properties, (Melbourne: Deakin University, Griffith University, 2019).
- 3 OH&S issues associated with plasterboard are outlined in: Department of Justice and Attorney-General, Workplace Health and Safety Queensland, *Manual handling plasterboard: Campaign report* (State of Queensland: 2013).
- 4 Safe work Australia, Work Health and Safety Perceptions: Construction Industry (Canberra: 2015).
- 5 Plasterboard waste is estimated vary in research but have been estimated to between 10 and 18%. Ana Jiménez-Rivero, Ana De Guzmán-Báez and Justo García-Navarro, "Enhanced On-Site Waste Management of Plasterboard in Construction Works: A Case Study in Spain," *Sustainability* Vol.9, Issue 3 (2017): 450, https://doi.org/10.3390/su9030450
- 6 Rayan H. Assaad et al., "Quantification of the State of Practice of Offsite Construction and Related Technologies: Current Trends and Future Prospects," *Journal of Construction Engineering and Management*. (May 2022): 148, 04022055. 10.1061/(ASCE)CO.1943-7862.0002302.
- 7 Shane Murray, "Design Research: Translating theory into practice," in *Design Research in Architecture: An overview*, ed. Murray Fraser (Farnham, UK: Ashgate, 2013), 95-116.
- 8 Anecdotal evidence from industry partners, based on Lendlease project experience. This is supported in research, for example: Sandanayake et al., "Residential building defects investigation and mitigation," 3689-3711.
- 9 Anthony Mills, Peter Love and Peter Williams, "Defect Costs in Residential Construction," Journal of Construction Engineering and Management. 135(1) (January 2009): 12, 16, DOI:10.1061/(ASCE)0733-9364(2009)135:1(12)
- 10 Sandanayake et al., "Residential building defects investigation and mitigation," 3689-3711.
- 11 Sandanayake et al., "Residential building defects investigation and mitigation," 3689-3711.
- 12 Hefferman, M. Victoria won't follow NSW on building defects reform, The Age, January 18, 2022
- 13 Johnston and Reid, An Examination of Building Defects.
- 14 Johnston and Reid, An Examination of Building Defects, 30.
- 15 Duane Roskoskey, Drywall Recycling Management Guide. (Michigan: Michigan Department of Environmental Quality, 2007).
- 16 Joe Pickin et al., National Waste Report 2020 (Docklands: Department of Agriculture, Water and the Environment; Blue Environment, 2020). This estimate excludes mining and other industrial wastes for which little data is available. Mining waste is estimated to be around 500Mt, seven times that of Australia's general waste.
- 17 The waste hierarchy developed from the European Union Waste Framework in the 1970s and has been widely adopted worldwide to establish priorities for waste management. The principles adopted in Australia's National Waste Action Plan 2019 are based on the waste hierarchy.
- 18 Science and Technology Select Committee, Off-Site Manufacture for Construction: Building for Change (London, UK: House of Lords, 2018).
- 19 "Recycling Modernisation Fund," Department of Climate Change, Energy, the Environment and Water, Australian Government, https://www. environment.gov.au/protection/waste/how-we-manage-waste/recycling-modernisation-fund/state-territory-agreement-announcements
- 20 Department of Sustainability, Environment, Water, Population and Communities, *National Waste Policy Case Study: CSR Gyprock™ take-back scheme for gypsum board product* (Commonwealth of Australia: 2011).
- 21 "Cross-industry joint venture to build new plastic recycling facility," Cleanaway, 2021, https://www.cleanaway.com.au/sustainable-future/crossindustry-jv-plastic-recycling-facility/
- 22 "National Waste Policy Action Plan 2019," Australian Government, state and territory governments and the Australian Local Government Association, 2019, 1–41. https://www.dcceew.gov.au/sites/default/files/documents/national-waste-policy-action-plan-2019.pdf
- 23 Safe work Australia, Work Health and Safety Perceptions.
- 24 Department of Justice and Attorney-General, Manual handling plasterboard.
- 25 Safe work Australia, Work Health and Safety Perceptions.
- 26 Assaad et al., "Quantification of the State of Practice."
- 27 Assaad et al., "Quantification of the State of Practice," 7.

Bibliography

- Assaad, Rayan H.,Islam El-adaway, Makarand Hastak and Kim Needy. "Quantification of the State of Practice of Offsite Construction and Related Technologies: Current Trends and Future Prospects," *Journal of Construction Engineering and Management*. (May 2022): 148, 04022055. 10.1061/(ASCE)CO.1943-7862.0002302.
- Australian Government, state and territory governments and the Australian Local Government Association. "National Waste Policy Action Plan 2019." dcceew.gov.au, 2019. https://www.dcceew.gov.au/sites/default/files/documents/national-waste-policy-action-plan-2019.pdf
- Cleanaway. "Cross-industry joint venture to build new plastic recycling facility." cleanaway.com.au, 2021, https://www.cleanaway.com.au/ sustainable-future/cross-industry-jv-plastic-recycling-facility/
- Department of Climate Change, Energy, the Environment and Water, Australian Government, "Recycling Modernisation Fund." dcceew.gov. au. https://www.environment.gov.au/protection/waste/how-we-manage-waste/recycling-modernisation-fund/state-territory-agreementannouncements
- Department of Justice and Attorney-General, Workplace Health and Safety Queensland. *Manual handling plasterboard: Campaign report*. August 2013. State of Queensland: 2013.
- Department of Sustainability, Environment, Water, Population and Communities. *National Waste Policy Case Study: CSR Gyprock™ take-back scheme for gypsum board product.* Commonwealth of Australia: 2011.
- Jiménez-Rivero, Ana, Ana De Guzmán-Báez and Justo García-Navarro, "Enhanced On-Site Waste Management of Plasterboard in Construction Works: A Case Study in Spain," *Sustainability* Vol.9, Issue 3 (2017): 450, https://doi.org/10.3390/su9030450
- Johnston, Nicole and Sacha Reid, An Examination of Building Defects in Residential Multi-Owned Properties, Melbourne: Deakin University, Griffith University, 2019.
- Mills, Anthony, Peter Love and Peter Williams. "Defect Costs in Residential Construction." *Journal of Construction Engineering and Management*. 135(1) (January 2009): 12, 16, DOI:10.1061/(ASCE)0733-9364(2009)135:1(12)
- Murray, Shane. "Design Research: Translating theory into practice." in *Design Research in Architecture: An overview*. Edited by Murray Fraser, 95-116. Farnham, UK: Ashgate, 2013.
- Pickin, Joe, Christine Wardle, Kyle O'Farrell, Piya Nyunt, Sally Donovan. National Waste Report 2020. Docklands: Department of Agriculture, Water and the Environment; Blue Environment, 2020. http://www.environment.gov.au/protection/waste/national-waste-reports/2020.
- Roskoskey, Duane. Drywall Recycling Management Guide. Michigan: Michigan Department of Environmental Quality, 2007. https://www.michigan.gov/-/media/Project/Websites/egle/Documents/Policies-Procedures/MMD/Op-Memo-111-23.pdf?rev=848919f0b43d4d38ab8d93912f68e70d
- Safe work Australia. Work Health and Safety Perceptions: Construction Industry. Canberra: 2015.
- Sandanayake, Malindu, Wei Yang, Namita Chhibba, and Zora Vrcelj. "Residential building defects investigation and mitigation a comparative review in Victoria, Australia, for understanding the way forward," *Engineering, Construction and Architectural Management*, Vol. 29 No. 9, (2022): 3689-3711. https://doi.org/10.1108/ECAM-03-2021-0232
- Science and Technology Select Committee. Off-Site Manufacture for Construction: Building for Change. London, UK: House of Lords, 2018. https:// www.parliament.uk/documents/lords-committees/science-technology/off-site-manufacture-for-construction/off-site-manufacture-construction-ev. pdf.

7.1 Provocations: design and assessment

7. APPENDIX


The appendix collects significant bodies of work in relation to key research activities including the detailed drawings and testing of the provocations; the full review of exemplars; performance testing, life cycle evaluation and material costs undertaken by University of Melbourne; the summary of the literature review and a record of interviews and workshops undertaken.


- 7.1 Provocations: design and assessment
- 7.2 Exemplars and alternatives
- 7.3 Performance and life cycle
- 7.4 Workshops and outcomes
- 7.5 Interviews
- 7.6 Student work from studies unit Wall Party!

7.1 Provocations: design and assessment


7.1 Provocations: design and assessment

PROVOCATION 1: IMPROVED BAU






Improved Status Quo




7.1 Provocations: design and assessment

PROVOCATION 1: IMPROVED BAU

Construction Sequencing: Business as usual





Construction Sequencing: Improved Business as Usual




7.1 Provocations: design and assessment


PROVOCATION 2: PERFORMANCE CORE






Inter-tenancy Wall Type






Less manual lifting handling - improved OH&S




Removable wall panels

Continuous Sleeve Unit with Durra Panel





Continuous Sleeve Unit with Durra Panel




Product Name	Durra Panel S50 Plain
Nominal Thickness	50mm
Weight	18.5 kg/m² (nominal)
Width (Standard)	1187mm
Maximum Length	3600mm
Face Colour	Brown (Kraft liner)
Strength	Point load 5.8kN
Impact Resistance	High
Thermal Conductivity	0.081 W/mK
Thermal Resistance	0.62 m²W/k
Specific Heat Capacity	1050 J/kgK
Embodied Energy	12.6 MJ/m ²
VOC Emission rate (ASTM D5116)	<0.05 mg/m²/hr (7 days)
Biscuit Slots	Available


Provides 60 minutes FR


7.1 Provocations: design and assessment

PROVOCATION 2: PERFORMANCE CORE

Construction Sequencing








waste


trade complexity on site

7.1 Provocations: design and assessment


PROVOCATION 3: PLUG-N-PLAY




Plug-n-play



Plug-n-play Raised Floor



Plug-n-play Suspended Ceiling




Plug-n-play Exploded View


7.1 Provocations: design and assessment

PROVOCATION 3: PLUG-N-PLAY

Construction Sequencing: Plug-n-play





ISSUES




7.1 Provocations: design and assessment

PROVOCATION 4: NO WALLS







No walls



100% off-site

Inter-tenancy Wall Type







7.1 Provocations: design and assessment


PROVOCATION 4: NO WALLS

No Walls Back-to-Back Kitchen Pod

No Walls In-Line Kitchen Pod




No Walls Robe Storage with Sliding Door




7.1 Provocations: design and assessment

PROVOCATION 4: NO WALLS

Construction Sequencing: No Walls








alimak

7.2 EXEMPLARS AND ALTERNATIVES


This appendix details each of the exemplars studied through drawings and images.








337625

BADASA









13


CRC#28 COMP ON ENTISED INTERNAL WALL SYSTEM S FOR MUUTI-RESIDEN TIAL APPLICATIONS


COMMERCIAL MODULAR SYSTEMS

modular office fibrat furniture demountable buildings ponclised wall systems local modular buildings





<page-header><page-header><page-header>




































ntumeet monufacturing new materials and recycling dip systems- interchangole

AND PERFORMANCE


joints performace-fire, acoustic, thermal, odour








advanced menufacturing new materials and recycling clip systems-interchangole joints















7.3 PERFORMANCE AND LIFE-CYCLE


This appendix contains an analysis of the performance requirements for internal walls.






















 (2) Life Cycle Inventory (LCI) 2.3 - System description for the waste management scenarios The different treatment constitution for the management of the wastes generated at the building site are described as follows: Lond(N) all the wastes are disposed to lendfill. Accepting: recyclible wastes are served an encycling plant, non-recyclable wastes are serve to a nicheration plant and non-recyclable or incinemble wastes are set to an incinemation plant and non-recyclable or incinemble wastes are set to an incinemation plant and non-recyclable or incinemble wastes are set to are diffil. Accepting: recyclible wastes are last infrastructure, the incinemation process, the electricity generated and the disposel of sales. Electrical energy recovery (calculated from calculity wiles deta) and the amount of residual ashes (which are disposed by landfill) are also considered. 	65	 (3) Life Cycle Impact Assessment (LCIA) The Environmental Anglormance to Construction (ENC) database will be used to obtain the investory data of the processe involved in the study. These processes was adapted on the Automilan system. The quality requirements related to the data used are defined by the following parameters: Bagion of the scenario: Sydney, Melbourne and Brisbane. Geographic field: mixed technology. 	66
 (4) Interpretation Use optic interpretation is a systematic technique to identify, quantify, check, and evaluate information from the results of the LCI and/or the LCM. The outcome of the interpretation phase is a set of conclusions and necommendations for the tudy, According to ISO 340402006, the interpretation should include the following: Managing and interpretation the results from the LCI or LCM phase. In order to help determine the significant issues, in accordance with the goal and scope definition and interactively with the evaluation element. Branchoton, Establish and enhance confidence in, and the reliability of the results of the LCA or the LCI study. Including the significant issues identified in the first element of the interpretation. Conclusions, Bratistions, and recommendations for the interded accience of the LCA. 	47	 References Injertifuk, Krawster, S., Nay, T., Minsler, N., Braves, K., & Ang, L. (2008). Unsystematic and Gravitantic buildings. The Anther Science of Sciences and Gravitantic buildings. 2011;100:06. Origo, R., Rogardina, J., C., Hang, R., & Carati, K. (2008). The analysis of the construction formation of Sciences and Benergy and Sciences and Benergy and Benergy 2012;100:06. Carathe, K., Canada, M., & Carati, K. (2008). The analysis of the science of Benergy 2012;100:06. Carathe, K., Carathe, K. (2008). Unstanded and Benergy 2012;2012;2012. Carathe, K., Carathe, K. (2008). Restances and Sciences and Benergy 2012;100:07. Carather, K., Carathe, K. (2008). Restances and the science of the science of Benergy 2012;2012;2013;2013;2013;2013;2013;2013;	68


7.3 PERFORMANCE AND LIFE-CYCLE

This appendix contains an summary of research undertaken into life-cycle assessment tools.





ASSESSMEN	T METHODO	LOGY	-West	ENGINEERING PE	ERFOR	MANCE			.12	1
	Engineering Botton	a Line Overview :		_		Speol	floc		- V	X
			at		Main Inda	at an	Hadita		Design	
			17		Level of the re	wistance.	Decomposition tempe BAL 29 Fee Webstand	etare (%)	Miners Seller	
					Range		ISAL 20 Pice Widedand		Deliber Deliberts	
									Dellar!	
LEVEL 1 Bottom	ino aci.	agineering Performance		,	Heat insulation	efficiency.	The Volume 1	ancos	Monets.	
			Next Texabelian				R - Value - Clermal (1	edu/Delty	Dellar	
LEVEL 2 Indicat	TR Level of File Residence	- Smith	R76Geecy							
	Desergenden	F				Engineering Pe	rformance Criter			4
LEVEL 3 Motri	Tempetitet	Compressive & Tandla Straugh (MPA)	ReVelae			Decomposition Temperature	Compressive (MP4)	Terete-strength ONFIG	8.Value	1
				Busers 5 B	with manage	100 %	15 MPa	0.PH0 1.58 MP4	0.68	4
						RFP: 00 min		1.00 8878		
				Score 0 P	Performance	808 %	1MPa	0.5 MPs	0.08	1
						Cannot hold shape in BR.				I
						20.0%				
1. N.				6. M. N. N.						
A COLORADO										






VIRONMENTAL PERFOR	MANGE		ENVIRONMENTAL I	PERFORMANCE	
	Specifics	a station of the		Results	1. A A A A A A A A A A A A A A A A A A A
Nain Indianar Stratificate gas esta para	Indicator and Metrics	Demision		Amount of CO ₂ emissions im3	Percentage of material recycled (%)
Recyclaridity	Percentage of material recycled (%)	Exter Mark Is Exter	Alaminium Haneycomb	2184.2 kg C0prq/m ³	70%
			Callaisse tibre certerit	76.4 kg COyeq/m ³	60%
Succ 1.Pederman Root 1.Pederman	Environmental Scoring Criteria America Company of Manager Company Notember 1 August 1997	enigalieni (%) (XCM) (M)	Faem Concrete	196.9 kg C0prq/m ³	93-98%
			Gypnum Board	301.8 kg C0 ₂ eg/m ³	70%
A			N 1 2 2 2		
		25	we have		












**





Introduction

- Recent study by UoM compared the IRe-cycle greenhouse gas emissions (LCCHGE) and IRe-cycle cost (LCC) of CLT and traditional reinforced concrete (RC) residential buildings for three class in Australia (Melbourne, Sydney and Bilsbane).
- Life cycle analyses were conducted within the boundaries of the product and construction, operational and maintenance (OSM), and end of life (EOL) phase
- The results are compared with a conventional RC building with a similar size, height and layout.

Method

Assumptions and justifications for the analyses are provided as follows:

The discount rate was assumed to be 7% based on infrastructure Australia (Assessment framework, 2018).

Life cycle performance of Cross Laminated

Timber mid -rise residential buildings in Australia

- > The concrete waste was assumed to be sent to lend®I as suggested by (Senamine et el., 1994)
- > The CLT vestes were assumed to be incinented as they are not suitable for landfill because they contain chemicals for termite protection (Oliveria et al., 2018).
- The locations of the building were assumed to be in the central business district (CBD) of each city.
- CI,T components were assumed to be supplied from an existing manufacturar located in Wodongs. Therefore, the transportation distances to the Melibourne, Sydney and Brisbane CBD were estimated as 323 km, 560 km and 1335 km, respectively.
- The transportation distance from the concrete supplier to the construction site was essured to be 80 km.
- The construction time of CLT building was taken as 30% less than that of the RC Building (Youman & Ritche, 2018).

Case study building


- The area and height of these buildings are 155m2 and 25 m, respectively.
- The ground floor and foundation of both buildings is traditional RC.
- The thickness of the ground floor stab in RC building is 300 mm. The stab thickness of Level 2-7 of the RC building is 250 mm.
- While the CLT building foor is constructed with 115 mm thick Australian Radiate pine CLT panels (i.e. CL3/115). The roof of the CLT building is constructed with 105 mm thick Australian Radiate pine CLT panels (i.e. CL3/105) and corrugated metal cledding.
- Details on the external and internal wall, and wall
 finishes are provided in Table 1.

1. . J. F.

Anormalization pro- mi Anadoscon min. Al Open-Pall-Series Anadoscon mi min. Anadoscon mi		1. Henry John 20 an. 1. Parkin: 10 we 1. Parkin: 10 we 1. Parkin: Said-11
ne 1. Statement on 1. Statement of one 1. Partie based 2 we 1. Partie based on on 1. Partie based on on		ann. 1. Ionalaiter 130 mer 1. Planarisanderi son.
3. Insubstantia mer		
3. Insubstantia mer		
		A fried staffing Parties 3. Strid staffing ware
1 miletonentitum 1 mainten 8 mil		1 Parton deput Street 6 regulation Street 3 Concernin (10 mer
1. Participanti di con 1. Inscheller II. enn 1. Statutati di con 4. SElle confe		1 Martin beaut Mine 2 majatar Tiree 4 manual PM Ion 4. Miner print 1 Materia and
Tel Intel BUT		
s or pasients 3 installer Wines		1-Council (1) Inc. 1-Installer INF INF 1-Pathology (1) Inc.
1. Company of the life 2. Seculation of the 3. C/J pater (10) was		
	2 malaten 8 m. 3 typople (Bine 1 area bine) 2 and a second second 3 malaten 8 m.	A majerie litro A Raydel litro A Raydel Litro Son Banna de litro A Standard anno A Standard A Standard A Standard A Standard A Standa


Case study building

 Two mid-to-high rise eight-storey residential RC and CLT buildings with similar dimensions were selected for LCOHOE and LCC analyses in this investigation (Fig. 1).
 Schematic discram of the case study building; a) 3D view; b) clan view; and c) elevation view.



Case study building

- These case skudy residential buildings were categorised as NCC Class 2 buildings and designed according to the Australian standard AS/NZS 1170; utimate limit state and serviceability.
- To account for the deemed to satisfy condition in National Construction Code (NCC), the fire
 resistance level of the CLT wall and foor was considered as 95/60/50 min, respectively for
 structural resistance/r
- The 278 mm well thick-ness, which includes the 115 mm thick Cl, T panel, floor thish and 113 mm ceiling with its cavity, satisfy the NCC accusic and vibration others for floors (Pagnancelli and Mamire, 2018).




NA CL

44

47


- CLT building has less initial cost than that of RC building, the savings ranging from 8-10%, depending on the city. During the operation phase, the CLT building was found to be 13-16% more expensive than the RC option.
- The lower densition, transportation and recycling cost of CLT over RG building at the end-of-life phase can be primarily attributed to the lighter weight of CLT.
- o. The total life cycle cost of CLT building is 0.9-1.3% lower than that of the conventional RC building.

14 . That a





Defining circular loops through continuous engagement with Customers



Scoring System: No = 0, Somehow = 1, Yes = 2


inem 2014 - Dahmlar för denkederand sor bism



The Wedge Dowel Concept



Same little Oderatikan on in Kinatikera from exact interesting



Circularity principles for internal walls?

- Long service life
- Location specific
- Adaptability limits Volume to cost ratio
- * Standardisation vs identity

Understand - Get to know the user and the

system Define - Put into words the design challenge

Define - Fut into worth the designer and your intention as the designer Mako - Honte, design, and prototype as many iterations and ventices as you can Release - Launch your design into the wild and hold your marative - owned loyaby in customers and deepen investment from atakaholders by telling a compelling story

Etc...

.


IDEO's Design Guide

THE CIRCULAR DESIGN GUIDE





Can this lead to circular product development or to the definition of company-level circular design guidelines?




7.4 Workshops and outcomes **EP1** documentation

CRC#28 - Componentised internal walls for multi-res

Expert panel workshop 1

Panel:	Lendlease:	invited experts
	Karl-Heinz Weiss	Prof. Nigel Bertram
	Steven Huang	Prof. Shane Murray
	Daiman Otto	Prof. Daphne Flynn
		Dr. Rowan Page
2		Dr Rachel Couper
. C	Uni of Melbourne:	David Cracknell (Lendlease)
	Tuan Ngo	
	Xuemei Liu	
	Yousef Alqaryouti	[By interview]
		Adjunct Professors
	Monash:	Kirsten Thompson
	Lauta Harper	Rob McGauran
	Lee-Anne Khor	Geoffrey London
	Duncan Maxwell	Lendlease:
	Victor Bunster	Mario Lara Ledermann
	Ivana Kuzmanovska	Daryi Paterson
-	Jean-Paul Rollo	Steve Gradier
	Problem definition & discussion	
11.00am	Welcome	5 min
11.00am 11.05pm		15 min
Session 1: 11.00mm 11.05pm 11:25pm 11:30pm	Welcome Lendlease presentation, Karl-Heinz	5 min 15 min 5 min 30 min
11.00am 11.05pm 11:25pm	Welcome Lendlease presentation, Karl-Heinz Summary by research team	15 min 5 min 30 min
11.00am 11.05pm 11:25pm	Welcome Lendlease presentation, Karl-Heinz Summary by research team	15 min 6 min 30 min 2-3 small group
11.00am 11.05pm 11.25pm 11.30pm	Welcome Lendlease presentation, Karl-Heinz Summary by research team Discussion	15 min 6 min 30 min 2-3 small group
11.00am 11.05pm 11.25pm 11.30pm 12:00pm	Welcome : Lendlease presentation, Karl-Heinz Burnmary by research team Discussion Small group reporting / discussion	15 min 6 min 30 min 2-3 small group
11.00am 11.05pm 11:25pm 11:30pm 12:00pm	Welcome : Lendlease presentation, Karl-Heinz Summary by research learn Discussion Small group reporting / discussion Break – 10 minutes	15 min 5 min 30 min 2.3 small group 20 min
11.00am 11.05pm 11.25pm 11.30pm 12:00pm 12:20pm Session 2:	Welcome : Lendlease presentation, Karl-Heinz Burnmary by rosearch learn Discussion Gmail group reporting / discussion Break – 10 minutes Exemplars and elematives	15 min 5 min 30 min 2.3 small group 20 min 20 min
11.00am 11.05pm 11.25pm 11.30pm 12:00pm 12:20pm Session 2: 12:30pm	Welcome Lendlease presentation, Karl-Heinz Burnmary by rosearch learn Discussion Small group reporting / discussion Break – 10 minutes Exemplars and alternatives Recap of discussion paper	15 min 5 min
11.00am 11.05pm 11.25pm 11.30pm 12:00pm 12:20pm Session 2: 12:30pm	Welcome Lendlease presentation, Karl-Heinz Burnmary by rosearch learn Discussion Small group reporting / discussion Break – 10 minutes Exemplars and alternatives Recap of discussion paper	15 min 5 min 2-3 small group 20 min 20 min 10 min 30 min


Framework for responses



SESSION 1: **ISSUES + OPPORTUNITIES**

ow did we get here? • From your disciplinary perspective, what are the current issues and benefits of plasterboard walls?

What does the group see as the key issues? • How can we effectively frame the argument? current research gaps? • What kind of evidence / analysis do we need to undertake to make our case?



ura Harper ctor Bunste

Allen and in



7.4 Workshops and outcomes

EP1 outcome summary

Can we reduce the amount of walls built – does this provide spatial benefits and cost benefits



Walls as a service – a subscription model



On-site experience demonstrates that the of typical plasterboard systems is always che – often half the time a

Once the stage of hanging plaster is reached, the process is fast

TIME

Innovative approaches to building sequencing & critical path planning

Models of digital integration from design to installation

The current skill-set and availability of trade labour to deliver the status quo is large and contractually interchangeable wet trades require mes, the setting of rimer coats and coats, mastic joints

What is the business viability for offsite facilities? This requires a large enough volume of work.

AVAILABILITY

The availability of common systems is known and there are many suppliers

g off-site, you ctory – space, idling. Off-site n relies on an lity being withi le distance fro



Could 'system' design be with the design of supply chains in a particular context

A resistance to change – currently there is a familiarity across the board – from clients, architects, uilding designers, bu nd building surveyors

Plasterboard is perfect for hiding all manner of ills, damage, and workaround It acts as the final layer of "polish", hiding everything behind it.

How can joints in wall systems become useful? live joints, lighting track

Explore the possibility of walls systems allowing for flexible rearrangement of interior spaces

So often, a suitable construction system is about the context. A 'system' will never fit every situation.

What is the lifespan requirement of interior wal systems

ADAPTABILTY

The standardisation and material modularity of the material provide a responsiveness of the product for different proje

The processing of plasterboard on site i.e. cutting and sanding can be a health issue

HEALTH

r future

Establish creat reason focused product development horizon with regards digital sensor integration — awareness c

Smart' systems integrating echnology into walls

The application of paint is another health hazard

The tolerance of junctions e.g. top and bottom

pair work is I to install or future servi

COMPLIANCE



stems allowing for

through al









What are the similarities between contexts? What are the things that everywhere has to deal with?


Increasing regulatory demands


Fire performance is questionable for demountable wall types





7.4 Workshops and outcomes EP2 barriers to adoption - diagram





7.5 Interviews

The record of transcripts from interviews is not available to the public.


7.6 Student work from studies unit Wall Party!

Monash Architecture Studies Unit

Catalogue


2021







id besiev P


institution for the second






































































formits 7-pine started 7-biter interior information and minima-



